No.	Items of work	Per	Quantity	Rate
	Wasteweir to the left 53 feet long R. L. 52·000.			
1	Earthwork excavation	C.yds.	79	
2	Dismantling damaged portion of returns and coping slabs of.	Lump	sum	
3	Burnt brick in surki mortar	C.ft.	294	
4	Re-fixing the old burnt stone slabs	S.ft.	44	
5	Burnt stone slabs roughly dressed new ...	,,	57	
6	Plastering with surki mortar	Sqr.	3 86	
7	Jelly concrete with surki mortar	C.ft.	112	
8	Rough stone work (new)	C.yds.	74	
9	Constructing a masonry retaining wall between old and new apron to the required level.	Lump	sum	

H. R. VENKATASUBBA RAO,
Executive Engineer

KOLAR DIVISION.

Dated 24th December 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., on 24th January 1929, for restoring Geraddi Tank Registered No. 48 of Sidlaghatta Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A M to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees (350) three hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed" Tender for restoring Geraddi Tank Registered No. 48 of Sidlaghatta Taluk in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9' The tenderers must quote specific rates for each item of work both in words and figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate rate will not be accepted.

Abstract estimate for restoring Geraddi Tank Reg. No. 48 of Sidlaghatta Taluk Kolar District.

Items of work	Per	Quantity	Rate	Cost	Total
Bund.					
Eathwork to bund including watering and tamping with all lead and lift.	C.yd.	7,630			
Puddle wall at scour portion ...	,,	103			
Eathwork for foundation of puddle wall ...	,,	79			
New stone revetment	,,	1,014			
Turfing	S.yds.	5,841			
Grade stones complete	Each	22			
Index stones	,,	22			
Registered No. and Date stones ...	,,	2			
Carving figures to existing B. M. stones ...	,,	2			
Gauge stone with carving figures ...	,,	1			
Total ...	...	..			
Sluice.					
Eathwork excavation	C.yd.	70			
Refilling with consolidation	,,	54			
Burnt brick in surki mortar... ..	C.ft.	424			
Concrete in surki mortar	,,	342			
Burnt stone slabs 6" thick	S.ft.	258			
Plastering with surki mortar... ...	Sqrs.	6·02			
Providing upper and lower orifice slabs ...	Each	2			
Providing plug and rod with locking arrangements.	,,	1			
Boring noles in slabs	L. S.				
Total ...	. .	...			
Weir.					
Earthwork excavation and using for flank bund including led lift.	C.yd.	98			
Earthwork and for flank bund ...	,,	422			
Turfing wings	Sqr.yds.	260			
Concrete in surki mortar	C.ft.	434			
Burnt brick in surki mortar	,,	874			
New stone work	C.yd.	120			
Old stone work	,,	79			
Burnt stone slabs 6" thick	Sq.ft.	360			
Plastering with surki mortar .. .	Sqr.	11·81			
Providing jaggles	L. S.	...			
Removing apron from old weir and dismantling masonry.	,,	...			
Removing and refixing available slabs ...	Sq.ft.	100			
Total ...	...	...	..	...	..

Notice dated 12th December 1928.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part VI, pages 1498 to 1499, dated 20th December 1928, calling for tenders for the Restorationof Brahmarahalli Doddakere, Regd. No. 592—235, of Srinivaspur Taluk. Last date for tender is 2 P.M. on 10th January 1929.

N. LAKSHMINARASIMHAIYA
Executive Engineer.